Date: 20 January 2020 at 16:02

To: Nicholas Warns nw@nicholaswarns.com

Dear Nick,

Vestry Windows

As requested we have inspected each window and confirm the points as discussed.

Each window contains clear and very pale tinted crown square leaded panes all supported by a very heavy external ferramenta with lead ties attached the panels. There is a rusting iron casement in the south facing window that we are told does operate but is in need of overhauling.

In the past, odd panes of glass have been replaced using clear float glass; as and when the window is conserved we recommend these are replaced using crown glass.

The estimated cost of releading both windows would be £6,500, this includes the overhauling of the iron casement.

The estimated cost of tipping each end of the ferramenta of which there are 322, using stainless steel of the same size, as well as shot blasting and re-coating using rust inhibiting paints would be a total of £4,830

To supply and fit black painted stainless steel guards to the individual main lights (11 in total) would cost a total of £2,730 All plus VAT.

Yours sincerely

Terry Devlin



Terry Devlin Devlin Plummer Stained Glass Orchard Farm Old Road Great Moulton Norwich NR15 2HA W 01379 677111 M 07808957075